COLLECTION OF CTL DECISIONS

Standard:	**Sub clause:**	**Sheet n. 316**
IEC 61010-1:1990+A1:1992+A":1995	14.7.2	**Page 1(1)**
Subject: Mains transformers Overload test	**Key words:** - Transformer - Overload - Temperature	**Decision taken by ETF3 and confirmed by CTL at its 38th meeting, in Toronto**

Question:

Should this test be performed starting from cold condition or from operating temperature?

Decision:

Tests from both temperatures are valid and should therefore, be performed if there is likelihood that limits will be exceeded.

Explanation

All working temperatures are addressed by this requirement. Laboratories should analyse the operation of the device to determine whether more than one test is needed.